



Village of Menomonee Falls
 W156 N8480 Pilgrim Road
 Menomonee Falls, WI 53051-3140
 Telephone: (262) 532-4200

Asbuilt

STORMWATER MANAGEMENT FACILITIES OPERATION AND INSPECTION REPORT

Quarter Section SW ¼ Sec 25 Name of Business/Subdivision TI Investors of Lilly Road LLC.
 Property Tax ID Number MNFV0099999005 Address of Property W140 N5998 LILLY ROAD
 Date 12/02/2016 MENOMONEE FALLS, WI
Zilber

| | |
|----------|---|
| Dry Pond | x |
| Wet Pond | |
| Other | |

Location of Pond Directly north of Union Pacific
Railroad track
parking lot drainage

Pond ID: SWP 255006


Year Pond Constructed 2016 Year of Last Certification none

| Compliance Verification | Design | Actual | Compliant | | Comments (Condition of Structure) |
|--|--------|--------|-----------|----|---|
| | | | Yes | No | |
| Primary Outlet Pipe | | | | | Outlet Pipe Material |
| Opening Diameter (inches) | 8 | 8 | x | | Plastic pipe, no visible cracks or defects. |
| Upstream Invert | 783.00 | 783.05 | x | | |
| Downstream Invert | 782.73 | 782.79 | x | | |
| Length (feet) | 110 | 110.1 | x | | |
| Slope (%) | 0.25 | 0.24 | x | | |
| Secondary Outlet Pipe (If Applicable) | | | | | Outlet Pipe Material |
| Opening Diameter (inches) | | | | | |
| Upstream Invert | | | | | |
| Downstream Invert | | | | | |
| Length (feet) | | | | | |
| Slope (%) | | | | | |
| Riser (If Applicable) | | | | | Riser Material |
| Opening Diameter (inches) | 8 | 8 | x | | Plastic pipe, no visible cracks or defects |
| Elevation | 785.20 | 785.23 | x | | |
| Upper Discharge Control (If Applicable) | | | | | CMP Pipe with honeycomb top. no visible cracks or defects |
| Opening Diameter (inches) | 24 | 24 | x | | |
| Elevation | 785.5 | 785.4 | x | | |



Inspection Firm: Pinnacle Engineering Group Inspector Name : Aaron E. Koch
Phone Number: 262-754-8888 Inspection Date: 11/30/16
Address: 15850 W. Bluemound Rd
Suite 210, Brookfield WI
53005

Certifying Professional *Aaron E. Koch*
Name:
Phone Number: 262-754-8888



| | |
|-------------------------|--------------------------|
| Date: <i>12/7/16</i> | Signature: <i>AEK</i> |
|-------------------------|--------------------------|

10-3-2012